APPENDIX -5
PRICE BID

Sl No.	Item Description	Item Specification & Work Description	Qty	Unit	Unit Rate Excluding GST (Rs.)	Total Amount Excluding GST (Rs.)	GST (%)	Total Amount Including GST (Rs.)
1	Supply of 2-Ton Split AC	Supply of one number wall-mounted split AC unit of 2-ton capacity(minimum), 5-star energy rating, 230 V, single-phase, R32 refrigerant or equivalent, copper condenser and evaporator coils, cooling-only operation.This includes Supply of Wireless Remote with batteries	1	No				
2	Dismantling, Removal of Existing AC and associated components	Dismantling and removal of the existing indoor and outdoor units, associated components, copper refrigerant piping and interconnecting cable, drain pipe including safe handling and shifting of dismantled materials to a location designated by KWML.	1	Job				
3	Installation of New Indoor and Outdoor Units	Installation, mounting and fixing of the new indoor and outdoor units, including standard mounting brackets, supports, clamps, fasteners, piping covers and other accessories required for a complete installation. The work includes ladder arrangement/scaffolding if required. It Excludes Sl No. 4, 5 & 6.	1	Job				
4	Insulated Copper Refrigerant Piping	Supply and installation of suitable size insulated copper refrigerant piping, including necessary fittings. All wall openings made for piping routes shall be properly sealed using suitable filling materials to ensure the room is airtight and prevent cold-air leakage.	16	Meter				
5	Interconnecting Electrical Cable	Supply and installation of suitable-size, multicolour, 4 / suitable core copper electrical cable, conforming to applicable installation standards. The cable shall be routed separately from the copper refrigerant piping, without joints, using suitable conduits and supports. All wall openings made for cabling routes shall be properly sealed using suitable filling materials to ensure the room is airtight and prevent cold-air	16	Meter				
6	Drain Pipe	Supply and installation of suitable drain piping of minimum 32 mm diameter, including all necessary fittings. The existing drain pipes of the remaining two AC units shall also be connected to the newly installed drain pipe. All wall openings made for piping routes shall be properly sealed using suitable filling materials to ensure the room is airtight and prevent cold-air leakage.	15	Meter				
7	Testing, Commissioning	Checking of electrical connections and cooling performance, commissioning of the newly installed AC unit.	1	Job				

Total Amount for entire quantity (Rs.) including GST in words :

1) The bidder shall quote item-wise rates and amounts. Rates shall include all materials, labour, installation and incidental expenses relevant to each BOQ item.
2) The above rate quoted must be all inclusive of P&F, freight,etc on door delivery basis.
3)Bidder must quote for all the line items.
4) Lowest bidder shall be identified based on overall L1 basis.
5)Warranty as mentioned in the scope of work Annexure A is applicable without any additional cost.
6)The specified lengths of piping, cable and drain pipe are provisional maximum quantities. Any variation shall require prior approval from KWML and shall be paid at the quoted unit rates.
7)No separate payment shall be made for standard mounting accessories, supports, fasteners, clamps, piping covers or other items already included in the installation item.

Authorised Signatory

Name :

Designation:

Signature: